



PUBLIC WORKS DEPARTMENT

TOWN OF WINCHESTER

189 Rowley Street

Winsted, CT 06098

Phone (860) 379-4101 Fax: (860) 738-3509

2022 Road and Infrastructure Improvement Bond

Road Segment Information Sheet

Elm St Phase 2

From	Main Street	To	Center St
Improvement Scheduled		FY 2024	
2019 Paser Rating		Fair (4)	
Estimated Cost/Town Share	\$200,000	\$200,000	

Description of Existing Conditions

Pavement – The surface is map cracked. Recent Utility work has left significant patching along its length.

Drainage

Surface flow – slope on Roadway keeps water from ponding. The curb reveal is very low which limits the capacity of flow in the gutters.



Inlets – The catch basin inlet are in poor condition.

Pipes – The pipes are in poor condition.

Sidewalks – The sidewalks are in generally poor condition having been overlayed with asphalt and are made of several different materials.



Photo 1. Elm looking to Main

<p>Buried Utilities</p> <p>Water – The water is in good condition.</p> <p>Sewer – The sewer pipe is in poor condition.</p> <p>Eversource Gas – Gas Main has recently been replaced.</p> <p>Other – Frontier has completed some work on communications and the DOT has completed replacing the traffic signals and traffic sensing system.</p> <p>Other Considerations – This work continues work in the neighborhood on Center, Gay, Case and Elm.</p> <p>This is a local collector road leading to Main St and is an important route to Pearson School.</p>	 <p>Photo 2.</p>
<p>Proposed Improvements</p> <p>Description of Work</p> <ol style="list-style-type: none"> 1. The Sidewalks and curbs will be replaced. 2. The road will have a deep mill to regain curb reveal. 3. 2" of asphalt will be added to the milled surface. <p>Status of Design –Final design is ready to begin.</p> <p>Budget for Improvements</p> <p>Preliminary Cost Project Est - \$200,000</p> <p>Utility Participation: to be determined.</p> <p>Total Town Share Estimate - \$200,000</p>	 <p>Photo 3.</p>