



PUBLIC WORKS DEPARTMENT

TOWN OF WINCHESTER

189 Rowley Street

Winsted, CT 06098

Phone (860) 379-4101 Fax: (860) 738-3509




2022 Road and Infrastructure Improvement Bond			
Road Segment Information Sheet			
Marshall Street			
From	Colebrook Rd	To	Town Line
Improvement Scheduled		FY 2023	
2019 Paser Rating		Very poor (2) to Poor (3)	
Estimated Cost/Town Share:	\$795,000	\$795,000	
Description of Existing Conditions			
<p>Pavement – The surface is alligator and map cracked. Severe potholes form along the length of the road. Skim coating the road in spots has improved ridability. This is a temporary fix.</p>			
<p>Drainage</p>			
<p>Surface flow - significant ponding of surface water occurs along the shoulders.</p>			
<p>Inlets - The catch basin inlets are open top or more modern concrete. Selective improvements are needed.</p>			
<p>Pipes - The pipes are typically concrete and some corrugated metal pipe. Most pipe are terminated at headwalls. The headwalls are falling in and the pipes are mostly full of sediment.</p>			
<p>Sidewalks – There are no sidewalks on this rural road.</p>			

Photo 1.

<table><tr><td>Buried Utilities</td></tr><tr><td>Water – There are no water lines.</td></tr><tr><td>Sewer – There are no sewer pipes.</td></tr><tr><td>Eversource Gas – There is no gas in this Road.</td></tr><tr><td>Other –</td></tr><tr><td>Other Considerations – This work should be done with two other streets in the neighborhood: Old Colebrook Rd and Indian Meadow Rd. This approach saves money on cost to move the contractor on and off different locations.</td></tr></table>	Buried Utilities	Water – There are no water lines.	Sewer – There are no sewer pipes.	Eversource Gas – There is no gas in this Road.	Other –	Other Considerations – This work should be done with two other streets in the neighborhood: Old Colebrook Rd and Indian Meadow Rd. This approach saves money on cost to move the contractor on and off different locations.											
Buried Utilities																	
Water – There are no water lines.																	
Sewer – There are no sewer pipes.																	
Eversource Gas – There is no gas in this Road.																	
Other –																	
Other Considerations – This work should be done with two other streets in the neighborhood: Old Colebrook Rd and Indian Meadow Rd. This approach saves money on cost to move the contractor on and off different locations.																	
Photo 2. Looking North																	
<table><tr><td>Proposed Improvements</td></tr><tr><td>Description of Work</td></tr><tr><td>1. The Street Department has done selective improvements to the drainage system.</td></tr><tr><td>2. The project will be a full depth reclamation of the pavement surface with additional aggregate added.</td></tr><tr><td>3. 4” of pavement will be laid.</td></tr><tr><td></td></tr><tr><td></td></tr><tr><td></td></tr><tr><td>Status of Design – The work will be done off of State Bid. No design required.</td></tr><tr><td>Budget for Improvements</td></tr><tr><td>Drainage - Previously paid for from maintenance budget.</td></tr><tr><td>Reclaim and 4” of Pavement \$795,000</td></tr><tr><td></td></tr><tr><td></td></tr><tr><td>Total Estimate Costs - \$795,000</td></tr></table>		Proposed Improvements	Description of Work	1. The Street Department has done selective improvements to the drainage system.	2. The project will be a full depth reclamation of the pavement surface with additional aggregate added.	3. 4” of pavement will be laid.				Status of Design – The work will be done off of State Bid. No design required.	Budget for Improvements	Drainage - Previously paid for from maintenance budget.	Reclaim and 4” of Pavement \$795,000			Total Estimate Costs - \$795,000	
Proposed Improvements																	
Description of Work																	
1. The Street Department has done selective improvements to the drainage system.																	
2. The project will be a full depth reclamation of the pavement surface with additional aggregate added.																	
3. 4” of pavement will be laid.																	
Status of Design – The work will be done off of State Bid. No design required.																	
Budget for Improvements																	
Drainage - Previously paid for from maintenance budget.																	
Reclaim and 4” of Pavement \$795,000																	
Total Estimate Costs - \$795,000																	
Photo 3. At house 183 looking NB																	