



PUBLIC WORKS DEPARTMENT

TOWN OF WINCHESTER

189 Rowley Street

Winsted, CT 06098

Phone (860) 379-4101 Fax: (860) 738-3509



2022 Road and Infrastructure Improvement Bond			
Road Segment Information Sheet			
Newfield Rd			
From	Winchester Rd	To	Torrington Town Line
Improvement Scheduled		FY 2027	
2019 Paser Rating		2, 3 and 4	
Estimated Cost/Town Share		\$2,630,000	\$2,630,000
Description of Existing Conditions			
<p>Pavement – The surface is map cracked in the best locations and alligator cracked and potholed over significant portions. Numerous temporary patches have been laid to improve conditions</p>			
<p>Drainage</p> <p>Surface flow –the crown in the road is lower than desired to contain the drainage to the shoulders. Some rutting exist keeping water in the wheel tracks.</p>			
<p>Shoulders – are generally adequate, but in many instances too narrow. Guide rails are substandard in many locations.</p>			
<p>Inlets – There are limited catch basins on this section. Some sections require additional basins or existing ones rebuilt.</p>			
<p>Pipes – Cross culvert are the typical method of Pavement drainage. The condition of the pipes in not known. However, due to age, they should be replaced.</p>			
<p>Sidewalks – There are no sidewalks on this rural road. However, there is a fair amount of pedestrian traffic.</p>			

Photo 1. Looking North to Winchester Center

Buried Utilities	
Water – There are no water mains in this road.	
Sewer – There are no sewer mains in this road.	
Eversource Electric – The power lines are overhead.	
Other –	
Other Considerations – This is an important local road residents use to Torrington from Winchester Center.	<p>Photo 2 – Looking South</p>
Proposed Improvements	
Description of Work	<p>Photo 3.</p>
1. The cross culverts and associated structures will be replaced.	
2. The existing road surface will be reclaimed. Additional material will be added to the road base with the reclaimer.	
3. 4” of asphalt will be added to the surface.	
Status of Design – The decision on how to proceed with design and construction will be made at a later date.	
Budget for Improvements	
Preliminary Cost Project Est - \$	
State Participation: \$0.	
Total Town Share Estimate - \$2,630,000	