



## PUBLIC WORKS DEPARTMENT

### TOWN OF WINCHESTER

189 Rowley Street

Winsted, CT 06098

Phone (860) 379-4101 Fax: (860) 738-3509



2022 Road and Infrastructure Improvement Bond		
Road Segment Information Sheet		
Upland Road		
From		To
Main St		Spencer
Improvement Scheduled		FY 2024
2019 Paser Rating		Failed (1) from Main St to curve and Poor (3) to Spencer
Estimated Costs/Town Share	\$460,000	\$460,000
Description of Existing Conditions		
Pavement – A map and alligator cracked surface. Frequent potholes form across the road.		
Drainage		
Surface flow – Water flows in the gutters as intended; however, the crown of the road over most of its length is less than needed to keep the water at the side of the road.		
Inlets – There are no catch basin inlets. A few catch basins are needed to prevent water from flowing over the retaining wall.		
Pipes – There are no pipes currently.		
Sidewalks - The Sidewalks generally poor condition.		
Shoulders and Guide rails – The Main St shoulder is collapsing due to a failed retaining wall. The guide rails are all in poor shape incapable of proper function.		Photo 1. Interior Pipe View

Photo 1. Interior Pipe View

<p><b>Buried Utilities</b></p> <p>Water – The water lines are 1890s vintage cast iron pipes and are scheduled for replacement in FY 2022.</p> <p>Sewer – The sewer pipes are old clay pipe and require improvement; however, they can be repaired using trenchless methods.</p> <p>Eversource Gas – Eversource gas has planned improvements in 2022 over a small section starting from Spencer.</p> <p>Other – None</p> <p>Other Considerations – There is road utility and road restoration –work planned in the neighborhood on Spencer and Brookside St. This work will continue this work.</p>	 <p><b>Photo 2. Looking WB from Spencer to Curve</b></p>
<p><b>Proposed Improvements</b></p> <p><b>Description of Work</b></p> <ol style="list-style-type: none"> <li>1. Water and Sewer Commission will Replace Water Mains.</li> <li>2. Pipes and all catch basins will be added as needed.</li> <li>3. There will be a total reconstruction of the Road from Main St to the corner and mill and pave from the corner to Spencer.</li> <li>4. Work proposed for the existing sidewalks will be determined at a later date.</li> </ol> <p><b>Status of Design</b> – The paving work will be by State bid. Some retaining wall work will be completed by the Street Department.</p> <p><b>Budget for Improvements</b></p> <p>Preliminary Estimate \$460,000</p> <p>Utility Participation – (\$40,000) Approx.</p> <p><b>Total Estimated Town Share - \$460,000</b></p>	