

PUBLIC WORKS DEPARTMENT

TOWN OF WINCHESTER 189 Rowley Street Winsted, CT 06098 Phone (860) 379-4101 Fax: (860) 738-3509

| 2022 Road and Infrastructure Improvement Bond | | | |
|---|--------------|-----------|--|
| Road Segment Information Sheet | | | |
| Case Avenue Bridge | | | |
| | To Willow St | | |
| From Main Street Improvement Scheduled Improvement Scheduled | | FY 2024 | |
| 2019 Paser Rating | | Poor (3) | |
| Estimated Cost/Town Share \$2,250,000 | | \$450,000 | |
| Description of Existing Condition | | | |
| Pavement – The surface is alligator and map cracked. Potholes form along the length of the road. Drainage Surface flow – slope on Roadway keeps water from ponding. Inlets – There are no catch basin inlets. Pipes – There are no pipes. Sidewalks – The sidewalks are in generally poor condition. | | <image/> | |
| Bridge condition – The Bridge Deck is in poor condition. The substructure is in good condition, but, treatment is needed in order to extend its life. A Preliminary Engineer's report is available to describe its condition. | | | |

| Case Avenue Bridge | January 31, 2022 |
|--|---------------------------------------|
| Buried Utilities | |
| Water – The water is in poor condition. | |
| Sewer – The sewer pipe is in acceptable | |
| condition. | |
| Eversource Gas – Gas Main is scheduled to be | |
| replaced. | |
| Other – | |
| Other Considerations – This work continues work | |
| in the neighborhood. | NUL - MARK |
| | ALLE ANAL |
| | ASE CANAL |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | Photo 2. Looking at Southeast Wall |
| Proposed Improvements | , |
| Description of Work | |
| 1. The Bridge Deck will be removed and replaced. | |
| 2. The steel Beam substructure will be cleaned and | |
| re-coated. | |
| 3. The concrete abutments will have spot | |
| improvements to repair the concrete. | |
| 4. There will be a total reconstruction of the Road | |
| and Sidewalks from Main St to Willow St. | |
| 5. The bridge deck will be completely rebuilt. | |
| 6. The water and Sewer line will be replaced at this | |
| time. | |
| Status of Design – The Preliminary Engineering is | |
| complete. Final design has begun. | |
| Budget for Improvements | |
| The Bridge is being completed in the Federal Local | |
| Bridge Program that has 80% Federal and 20% | |
| Local Share. | |
| Total Construction Project Est - \$2,250,000 | |
| | |
| | |
| Total Town Share Estimate - \$450,000 | Photo 3. On Willow looking to Main |
| . , | I HOLD ST ON TYTILOW IOUNING TO MIAIN |